
From Tender to Deployment of Fiber

Tony Breach, Optical Network Manager

13. marts 2007

10101 11110
01101 10101
10011010010
0101010010001
1111010101001
1101010101010
00000 101010
01100 01101

Index

DF Specifications

Site Specifications

Acceptance Process

Service Level Agreement

Project Deployment

Lessoned Learned

Dark Fiber Specifications

DF spans


- Is the DF between adjacent sites used for active amplification of the signal
- The attenuation of a terrestrial span at 1550 nm shall not exceed 23 dB
- DF length shall not exceed 80 km
- The attenuation of a Submerged 1550 nm shall not exceed 26 dB

DF section length

- Consists of a number of DF Spans that connects two geographically specified POP's
- A DF section shall be less than 1200 km.
- Same ITU recommendation shall be valid for a DF Section

Uninterrupted fibre

- **A DF span shall consist of an uninterrupted glass fibre E2E** ⚠




BOL and EOL DF Specifications

- Fibres shall be specified according to ITU-T 652 or 655 Fiber recommendation
- Fibres installed after 1992
- Attenuation at 1550nm and 1310nm ⚠
- Chromatic Dispersion at 1550nm and 1310nm ⚠
- Polarisation Mode Dispersion at 1550nm ⚠
- Bend losses and Seasonal variations in the fiber parameter
- Connector losses
- The attenuation for a connector splice ⚠
- Reflection
- Average DF Span splice attenuation
- Connection type according to ITU-T
- Reflection and attenuation for connections



Outside Cable Management


- Seen from an ILA or POP - East and west DF span cable must minimum have a horizontal or vertical separation of 5 m
- Exposed fibre part shall be secured with heavy armouring



Site Specifications

Housing facilities must fulfil basic Tele-housing standards

- Shall have a local and remote controllable security system
- Access possible for third parties 24 hours/day and 365 days/year
- Specify required floor space – with room for expansion
- Temperature and the relative humidity shall be controlled
- Power System
 - Resilient Power system following different traces
 - Power system backup
 - Protection Earth – Star Topology only
- Insure Proper cable management



Acceptance Process (1)

Acceptance of a DF span and a DF section

- E2E OTDR measurement between two ILA sites of the attenuation at 1310 nm and 1550 nm
- Complete documentation of each fibre pair is made by the Provider
 - Showing all splices, patches and attenuation values
 - OTDR traces shall be supplied in an electronic format
 - Labeling information
- Verification of interconnection between fiber sub contractors
- A geographical map showing the placement of the fibre trace and the network diversity



Acceptance Process (2)

Acceptance of a ILA or POP

- Site survey – Physical inspection (random check)
- Power test



Dark Fiber – Second Hand or ?

- Buying a brand new Car do you expect it to come with second hand tires?

- It's a new ballgame for the Fiber Suppliers
 - Fibers installed 5 to 20 years ago
 - Running Revenue – Small expenses



- Tuning ULH Transmission Equipment requires accurate fiber data – **Measured**
 - Attenuation
 - CMD
 - PMD
- **Measuring a 1000 km. DF Section – Cost 15.000 EURO**
 - Who should take this cost?
 - Fiber or the Equipment Supplier

Service Level Agreement

- Service Specification
- Delivery terms
- Uptime
- Response time
- Penalty and Compensation Model
- Escalations procedure

Project Management

Key Word >>> FLEXIBILITY

Steering Committee

- NORDUnet Project Manager
- Telenor Project Manager
 - Sub Contractors – Project Manager Eltel
- Alcatel-Lucent Project Manager
 - Sub Contractors Installation – Project Managers Eltel
 - Alcatel Lucent Commissioning Team

Project kick off Meeting and initial phase

- Every thing must be aliened and understood by all parties
 - The cable lug
- Resource demanding process


Running Project

- Problems, unforeseen tasks etc. Solve that by putting the different performing engineers together

Project Re-Cap

Rollout progress:

- [History / Recap](#)
- Project SR and FL start – mid October 2006
- Project SC start – mid January 2007
- [Achievements](#)
 - All HW deliveries has been on time.
 - LINK 1-2-3-4-5-6 Installed
 - LINK 1-2-3 Commissioned wk07 (wk02)
 - Acceptance docs will be distributed in wk09.
 - LINK 4-5-6 Commissioned in wk08/09
 - LINK 7-8-9 Commissioned in wk10/11
 - LINK 10-11 "Southern Cross" on track



Lessoned Learned

- Your organisation participating in the tender process must possess good knowledge about fiber optic and ULH transmission – In order to specify and validate the tender process
- Real fibre data are crucial – Can be the difference between a huge unforeseen extra cost and a business case on track
- During project kick off make sure that your Supplier Technical project implementation team are aware of all your requirements and KPI's – Put all of that into the first MoM
- Your organisation participating in the implementation process must also possess good knowledge about fiber optic and ULH transmission – In order to validate the sub and main deliveries
- Perform a complete inspection of the first deployed site before continue deployment – In order to correct for mirrored errors based on misunderstandings

End Of Presentation

Tony Breach
Optical Network Manager, M.Sc.EE
tony@nordu.net

